

# **TEST REPORT**

### CLIENT:

/LILITI					
Company:	Turf and Ivy Solutions	Report Number:	74113B		
Address:	5 Centerpointe Dr, Ste 400,	Lab Test Number:	3019-6606		
	Lake Oswego, Oregon 97035	Test Completion Date:	6/5/2018		
		Report Date:	6/18/2018		
		Page:	1 of 1		
Requested By:	Patricia Ochoa				

### TEST MATERIAL:

Material Type:	Synthetic Turf	Synthetic Turf			Date Received:	5/30/2018	
Material Condition:	EXCELLENT:	XXX	GOOD:	POOR:	REJ	ECTED:	
Turf ID:	Mother of Pearl	Mother of Pearl					
Infill:	None		•				

### TESTING METHODS DECLIESTED.

TEGING METHODO REGUESTED						
Testing Services Inc. was instructed by the client to test for the following						
Standard: ASTM F1551 Test Method: Standard		Test Method:	Standard Test Methods for Comprehensive Characterization of Synthetic Turf Playing Surfaces and			
			Materials: Suffix-DIN 18-035, Part 6: Water Permeability of Synthetic Turf Systems and Permeable Bases			

		Materials: Suffix-DIN 18-035, Part 6: Water Permeability of Synthetic Turf Systems and Permeable Bases
•		
SAMPLING PLAN:		

5	sampling i	Date:	5/30/2018			
	•	Specimen sampling is performed in the sampling department at TSI.				
	•	The sampling size of specir	The sampling size of specimens is determined by the test method requirements.			
	•	In the event a specific sampling size is not called for, a determination will be made based on previous testing experience, and approved for use by an authorized manager.				
	•	All samples are subjected to the outside environmental conditions of temperature and relative humidly.				
	•	Sample requiring pre-deter	nined exposure to specified environmental conditions based on a specific test method, take place in the departments in which they are tested			

# PROCEDURE:

This test method determines the rainfall drainage capacity (permeability) of the playing surface. Test data values represent drainage rates vertically thru the turf, and do not take into account the percolation properties of any infill, pad and/or an underlying sub base. Three specimens, 11.5" diameter, were cut from the 15' turf roll, side-center-side manner. Each turf specimen was securely fastened to the permeability tube using mechanical flanges, ensuring vertical water flow thru the product. The water was pumped into the tube faster than could exit, until the water level reached 6". The water source was shut off, allowing the accumulated 6" water level to recede. The recede was timed via stopwatch until the water level exited the turf. The flow time was recorded in seconds. This procedure was repeated a total of 4 times where, the first pass was for conditioning, with passes 2,3,4 used for averaging. This process was repeated on the remaining specimens.

# DEVIATION FROM TEST METHOD:

DEVIATION FROM TEST METHOD.	
	State reason for any Deviation from, Additions to, or Exclusions From Test Method.
	None

## TEST SUMMARY:

Specimen #	Drainage (Seconds)	gal/min/yd²	Rainfall Capacity (inches/hour)
1	100.3	20.1	61.8
2	60.2	33.5	102.9
3	60.5	33.4	102.5
Average			89.1 inches/hour

<u>Uncertainty:</u>
We undertake all assignments for our clients on a best effort basis. Our findings and judgments are based on the information to us using the latest test methods available.

TSI can only ensure the test results for the specific items tested.

Unless otherwise noted in the deviations sections of this report, all tests are performed in compliance with stated test method.

Test Report Approval:

Erle Miles, III, Lab Director Testing Services Inc.

TSi Accreditation: TSi is a certified independent testing laboratory by the Synthetic Turf Council



tsioffice@optilink.us