

TEST REPORT

CLIENT:

Company:	Turf and Ivy Solutions	Report Number:	67990B
Address:	5 Centerpointe Dr, Ste 400,	Lab Test Number:	2836-9366
	Lake Oswego, Oregon 97035	Test Completion Date:	7/11/2016
		Report Date:	7/20/2016
		Page:	1 of 1
Requested By:	Andrew Gao		

TEST MATERIAL:

Material Type:	Synthetic Turf		Date Received:	7/7/2016			
Material Condition:	EXCELLENT:	XXX	GOOD:	POOR:	REJECTED:		
Turf ID:	Serenity						

TESTING METHODS REQUESTED:

Testing Services Inc. was instructed by the client to test for the following					
Standard:	ASTM F1551	Test Method:	Standard Test Methods for Comprehensive Characterization of Synthetic Turf Playing		
			Surfaces and Materials: Suffix-DIN 18-035, Part 6: Water Permeability of Synthetic Turf Systems and Permeable Bases		

SAMPLING PLAN:

Sam

pling Date:		1	7/7/:	2016				
-					 			

- Specimen sampling is performed in the sampling department at TSI.
- The sampling size of specimens is determined by the test method requirements.
- In the event a specific sampling size is not called for, a determination will be made based on previous testing experience, and approved for use by an authorized manager.
- All samples are subjected to the outside environmental conditions of temperature and relative humidly.
- Sample requiring pre-determined exposure to specified environmental conditions based on a specific test method, take place in the departments in which they are tested

DEVIATION FROM TEST METHOD:

State reason for any Deviation from, Additions to, or Exclusions From Test Method.					
none					

TEST SUMMARY:									
TEST METHOD	TEST DESCRIPTION	TEST RESULT							
ASTM F1551; Suffix-DIN 18-035, Part 6	ASTM F1551; Suffix-DIN 18-035, Part 6 Average Rainfall Capacity (Water Permeability) 65.6 inches/hour								
*Test data values represent drainage rates for the	*Test data values represent drainage rates for the turf and infill only, and do not take into account the percolation properties of a sub-base or padding.								
Infill System: 1.2 lbs/ft²Silica Sand Tube: 10.75" OD 10.00" ID 8" Length (Beveled) Flange: 9.375" Diameter	# of Specimens (3) 11.5" Diameter Tube Index Mark: 6" Tube Flow Head: 2 Gallons	Tube Weight: 39 lbs Pre-Conditioning: none							

We undertake all assignments for our clients on a best effort basis. Our findings and judgments are based on the information to us using the latest test methods available. TSI can only ensure the test results for the specific items tested.

Unless otherwise noted in the deviations sections of this report, all tests performed are in compliance with stated test method.

Test Report Approval:

Erle Miles, Jr. VP, Testing Services Inc TSi Accreditation: Our laboratory is accredited by the US Dept of Commerce, National Institute of Standards and Technology: ISO/IEC 17025:2005. Our code # is: NVLAP 100108-0. TSi is a certified independent testing laboratory by the Synthetic Turf Council

Form:	Rev:	Revision Date:	Page 1 of 1	
Release Date:	Control Type: Electronic – Expires 24 hours after this date: Jul. 21, 16			
	Printed copies are uncontrolled			

OUR LETTERS AND REPORTS APPLY ONLY TO THE SAMPLE TESTED AND ARE NOT NECESSARILY INDICATIVE OF THE QUALITIES OF APPARENTLY IDENTICAL OR SIMILAR PRODUCTS. THESE LETTERS AND REPORTS ARE FOR THE USE ONLY OF THE CLIENT TO WHOM THEY ARE ADDRESSED AND THEIR COMMUNICATION TO ANY OTHERS OR THE USE OF THE NAME TESTING SERVICES, INC. MUST RECEIVE OUR PRIOR WRITTEN APPROVAL. OUR REPORTS, LETTERS, NAME, SEALS, OR INSIGNIA ARE NOT UNDER ANY CIRCUMSTANCES TO BE USED IN ADVERTISING TO THE GENERAL PUBLIC.

PO Box 2041 Dalton, GA 30722-2041 (706) 226-1400 tsioffice@optilink.us